



7100 Technology Drive
West Melbourne, FL 32904
1-800-422-6281

Service Bulletin

BKSB-1051
Issue Date 6/7/2017



Issue: Firmware inadvertently loaded into the wrong radio

Importance: Resolves ability to load firmware into the wrong radio

Affected Models: KNG-Pxxx, KNG2-Pxxx

Recommended Action: Follow instructions below

NOTE: THIS BULLETIN DOES NOT APPLY TO KNG-S MODELS

Lightning Light KNG2 Bulletin

- (1) 5.5.0c Lightning Light upgrade files for both the KNG and KNG2 can be inadvertently loaded into the wrong radio. If this happens, the radio can be powered off, put back into firmware update mode, and loaded with the correct firmware.
- (2) Starting with the 5.6.0 release Lightning Light upgrades will be correctly locked to their associated platform. However, anyone updating firmware from before 5.5.0c to 5.6.0 will first need to update to 5.5.0c.

